



CONCEPT DESIGN FEATURES

- The three sandstone support pillars denote the 3 armed forces and provide inside surfaces for installation of interpretive panels with carved outside surface patterns depicting the fabric of the ANZAC sock knitter
- Installation of a level surface for all ability pedestrian access to the memorial shelter, and ease of circulation during ANZAC memorial service
- Provide electrical cabinet for ANZAC memorial tea/coffee and PA facilities
- Sandstone paving defining the shelter form
- Memorial shelter provides shelter for the ANZAC memorial event
- Generous wide steps to front of memorial space for informal seating with tranquil views to the dam
- Textured concrete surface
- Retain and protect sculptural installations
- Align location of new memorial shelter with visual axis through sculptural installations across the dam

MANLY WARRINGAH WAR MEMORIAL SHELTER



northern
beaches
council



REMEMBRANCE SHELTER ARTIST IMPRESSION – FRONT VIEW
MANLY WARRINGAH WAR MEMORIAL PARK

20 JUNE 2018
DWG No: MW-WM-03
SHEET 3 of 3
SCALE: NTS





CONCEPT DESIGN FEATURES

- 1 The three sandstone support pillars denote the 3 armed forces and provide inside surfaces for installation of interpretive panels with carved outside surface patterns depicting the fabric of the ANZAC sock knitter
- 2 Installation of a level surface for all ability pedestrian access to the memorial shelter, and ease of circulation during ANZAC memorial service
- 3 Provide electrical cabinet for ANZAC memorial tea/coffee and PA facilities
- 4 Sandstone paving defining the shelter form
- 5 Memorial shelter provides shelter for the ANZAC memorial event
- 6 Generous wide steps to front of memorial space for informal seating with tranquil views to the dam
- 7 Textured concrete surface
- 8 Easy pedestrian access to grass area
- 9 Retain and protect sculptural installations
- 10 Access path reconstructed to 1:20 gradient and 2m wide for all ability access
- 11 Align location of new memorial shelter with visual axis through sculptural installations across the dam
- 12 Fill and turf sloped bank to increase usable grass level surface area
- 13 Rebuild sandstone wall to raise surface levels
- 14 Retain existing picnic shelter

